

Baldwin Hill Road South Paving & Related Work
Baldwin Hill Road South
Egremont, Massachusetts

ADDENDUM #1
June 18, 2018

The Original Bid Documents, including the Contract Documents, Specifications and Plans, are hereby amended as noted in this Addendum No. 1, dated June 18, 2018.

Contractor shall acknowledge receipt of this Addendum by inserting its number and date in the space provided in the Bid Documents.

1. Coordinate paving operations, including but not limited to, compaction over existing water main with the Egremont Water Department.
2. Item 7, Remodel Structure, is included in the base bid items if required for the replacement of existing drainage culverts in/out of existing drainage structures. As stated on the plans, the Contractor shall review various drainage system conditions with the Egremont Highway Department prior to construction and determine if drainage culverts require replacement (Item 4, 12" HDPE Drainage Pipe). If required for drainage culvert replacement, remodeling of the structure will be paid for under Item 7.
3. Shim/Leveling course material shall be M3.11.03, HMA Dense Mix. Superpave Items are not included in this contract.
4. Road may be temporarily closed during construction activities and reopened daily. Access to houses shall be maintained at all times. Coordinate temporary road closure with Town Highway Department, Police, Fire and residents. Notify 48 hours prior to closure.
5. The date and time of the bid opening remains unchanged.
6. Please acknowledge receipt of this Addendum #1 on the Bid Form.