

Town Hall driveway and parking paving

Proposed work:

Remove all existing asphalt appr. 1400 sq. ft. Excavate lawn area on island to construct additional walkway appr. 35ø x 5ø. Install 8ø of processed gravel for walkway base. Regrade all walkways, driveway and parking areas. Appr. 13000 sq. ft. Handicap parking area to be 521 CMR 23.00 ADA compliant. Pave all driveways and parking areas with 2 inches of binder and 1-1/2 Inches of Mass. top. All walkways to be paved with 1-1/2 inches of binder and 1-1/2 inches of Mass. top. Appr. 285 tons asphalt.

Thomas Reynolds
Buildings and Grounds Superintendent
Town of Egremont
(413) 528-0182 ext 18