

July 16, 2019

Boice Road - specifications

- Resurface Boice Road with 1 ½" HMA overlay with tack coat
- Approximately 1633 tons of HMA
- Approximately 900 gallons of tack coat
- Mill keyways/joints at Route 71 intersection, Alford Town line, at the Boice Road bridge transitions and Hickory Hill intersection.
- Adjust structure with 1 ½" riser/round (inspection manhole)
- Driveway aprons addressed as needed. Some are gravel, some are blacktop

James Noe
Egremont Road Superintendent
413-528-1106